



दूरध्वनी :022- 25331590

022-25364779

ठाणे महानगरपालिका

महानगरपालिका भवन, सरसेनानी जनरल अर्णकुमार वैद्य मार्ग, चंदनवाडी पाचपखाडी ठाणे-400602
THE MUNICIPAL CORPORATION OF THE CITY OF THANE

संदर्भ क्र/ ठा.म.पा/उप न अभि/वि/1462

दिनांक 05 / 12 / 2022

Ref./T.M.C./EE/ELE/

Date / / 2022

नोटीस

विषय :- ऊथळसर प्रभाग समिती अंतर्गत सिध्देश्वर तलावाजवळ तीन टाकी येथे पथदिपांचे नुतनीकरणांतर्गत नवीन LED दिवे बसविणे.

(अंदाजखर्च वस्तु व सेवा कर वगळून - रु. 1,66,174/-)

महोदय,

वरील विषयांकित कामाकरीता ठाणे महानगरपालिका विद्युत विभाग, संबंधित क्षेत्रातील मान्यता प्राप्त ठेकेदाराकडून टक्केवारी दराची मोहोरबंद दरपत्रके मागवित आहेत. सदर कामाची दरपत्रके दि.06/12/2022 ते दि.13/12/2022 या कालावधीत सकाळी 11.00 ते सायंकाळी 4.00 वाजेपर्यंत नागरी सुविधा केंद्र ठाणे महानगरपालिका ठाणे येथे स्विकारण्यात येतील. मुदतीनंतर आलेल्या दरपत्रकांचा विचार केला जाणार नाही. याची कृपया नोंद घ्यावी.

अटी:

- 1) उद्योग उर्जा कामगार विभाग, महाराष्ट्र शासना कडून देण्यात आलेला विद्युत ठेकेदारांचा अनुज्ञापत्राचा दाखला सादर करणे बंधनकारक राहील.
- 2) शासकीय, निम शासकीय व स्थानिक स्वराज्य संस्थाकडे समकक्ष काम पूर्ण केल्याचा दाखला सादर करणे बंधनकारक राहील.
- 3) GST नोंदणी दाखला सादर करणे बंधनकारक राहील.
- 4) भविष्य निर्वाह निधी नोंदणी दाखला सादर करणे बंधनकारक राहील.

सोबत: अंदाजखर्च

सही/-

सौ.शुभांगी केसवानी
उपनगर अभियंता (वि)
विद्युत विभाग, ठामपा.

ABSTRACT

Name of work : SITC new LED lights in teen taki area near Siddheshwar Lake during Renovation of Streetlights under Uthalsar ward committee.

Sr.No.	Description	Unit	Qty	CSR 2022-23	Rate	Total
1	Supply Installation Testing & commissioning of integral high pressure Die cast/extruded aluminium LED streetlights luminaire with proper heat dessipation & toughned glass protector or with yellowing injection molded polycarbonate cover having high light transmission index.The LEDs are provided with suitable lens for dispersal for achieving street light optics to ensure uniform light distribution.The LED fixture shall be designned for at least L70 life of minimum 50,000 burning hours at ambient tempreture not less than 35°C. the system wattage (fixture's total power consumption) should be be 60W. Details as per technical specification attached.	Each	18	MR	6064.00	109152.00
2	Supplying and erecting mains with 3x2.5 sq.mm FRLSH copper PVC insulated wire laid in provided conduit/trunking/inside pole/Bus bars or any other places as per specification No: WG-MA/BW	Mtr	450	1.3.6	93.00	41850.00
3	Supplying & erecting FRP box of size 150mm x 125mm x 100 mm, 2.7 mm thick complete on pole/wall as per specification No. CB-SB	Each	18	7.8.8	496.00	8928.00
4	Supplying, erecting & marking SPMCB 0.5A to 5A, C-series with rated short - circuit breaking capacity (Icn) 10kA in provided distribution board as per specification no. SW-SWR/MCB	Each	18	5.3.1	250.00	4500.00
5	Dismantling the existing W.T. fluorescent fitting/ S.V./ M.V. / M.H. lamp /LED fitting from pole with brackets complete.	Each	16	2.12.3	109.00	1744.00
					Total Rs.	166174.00

I / We agree to execute the above work at % above/ below/ at par the above estimate cost

Contractor